


Unit Coolers

Price Sheet

Unit Coolers



Information Notes

- 1. All unit coolers coils are factory pressure tested, using a two- stage test pressure. Coils are first pressured to 150 lbs. and submerged under water and increased to 400 lbs. for a visual test. The unit is then certified by quality control and shipped with a 5 lb. holding charge of dry nitrogen. Coils are tagged for shipment with warning label that coils are under pressure.
- 2. Coils are must be evacuated by the installing contractor, prior to charging the system.
- 3. All units are tested electrically, motors are run at the nameplate voltage, rotation and amps are recorded.
- 4. Just prior to crating or boxing for shipment, the unit nameplate is affixed to the unit, along with appropriate instructional and warning labels.
- 5. A & BOC series unit coolers are shipped upright on legs (legs are removable). The installer can lift unit in place with the shipping base for eace of installation.
- 6. Installation and maintenance manuals are included with each unit.

TERMS OF SALE - Net 30 days, FOB our plant **FREIGHT TERMS -** All shipments are FOB our plant, with freight allowance to the first destination within the continental United States, excluding Hawaii and Alaska on shipments of 600 pounds or more.